


SITE PLAN - PLUMBING
SCALE: 1" = 50'-0"


- KEYED DRAWING NOTES:**
- 1. PC SHALL DISCONNECT AND REMOVE EXISTING DOMESTIC CONCRETE METER VAULT AND REPLACE WITH NEW METER VAULT TO COMPLY WITH EAST COCALICO WATER AND SEWER AUTHORITY CONSTRUCTION STANDARDS AND DETAILS ON P-2. PC SHALL REMOVE EXISTING CURB STOP AND ABANDON EXISTING 4" DOMESTIC MAIN TAP LATERAL PER ECTA SPECIFICATIONS AT THE EDGE OF THE RIGHT OF WAY. PC SHALL PROVIDE NEW 6" DIP TAP LATERAL INTO THE EXISTING ECTA MAIN IN SOUTH REAMSTOWN ROAD. PROVIDE NEW CURB VALVE BOX.
 - 2. PC SHALL INSTALL NEW U/G 6" DIP FIRE MAIN UNDERGROUND TO BUILDING. INSTALL PER ECTA SPECIFICATIONS.
 - 3. EXISTING 4" DIP DOMESTIC MAIN U/G PIPING MAIN TO BUILDING SHALL REMAIN. PC SHALL RECONNECT NEW SUPPLY FROM NEW METER PIT TO EXISTING PIPE MAIN TO REMAIN. REMOVE EXISTING PIPE FROM POINT OF CONNECTION TO EXISTING DEMOLISHED METER PIT.

- GENERAL NOTES:**
- 1. THE CONTRACTOR SHALL COORDINATE AND SCHEDULE ALL WORK IN CONJUNCTION WITH THE ARCHITECTURAL DRAWINGS AS REQUIRED TO ACCOMMODATE PROJECT PHASING.
 - 2. REFER TO PROJECT PHASING DRAWING AND SCHEDULE. PROVIDE ALL LABOR AND MATERIAL NECESSARY TO ACCOMMODATE PROJECT PHASING. IT SHALL BE UNDERSTOOD, THE SPRINKLER SYSTEM SHALL BE FUNCTIONAL AT THE COMPLETION FOR THE NEW WORK AREAS IN EACH PHASE OF CONSTRUCTION AS REQUIRED. TEMPORARY CONNECTIONS AND MULTIPLE SYSTEM RECHARGES OR RE-WORK MAY BE REQUIRED (SEE NEW WORK PLANS). PC SHALL COORDINATE WITH AUTHORITY HAVING JURISDICTION FOR EXPECTATIONS AND APPROVAL.
 - 3. IT SHALL BE UNDERSTOOD, THE DOMESTIC WATER SHUTDOWN FOR THE METER VAULT INSTALLATION SHALL OCCUR TO HAVE MINIMAL IMPACT TO THE DISTRICT FUNCTIONS.
 - 4. ALL PATCHING & REPAIRING OF SURFACES AND SITEWORK LEFT OPEN DUE TO DEMOLITION OR REMOVAL OF EXISTING PIPING & EQUIPMENT SHALL BE THE RESPONSIBILITY OF THE PLUMBING CONTRACTOR. PATCH EXISTING CONSTRUCTION AS REQUIRED TO MATCH ADJACENT SURFACES OR TO RECEIVE NEW FINISHES AS SCHEDULED.
 - 5. THE PLUMBING CONTRACTOR IS RESPONSIBLE FOR ALL CUTTING, PATCHING AND EXCAVATION AND BACKFILLING WITHIN THE BUILDING REQUIRED TO COMPLETE ALL INDICATED WORK. PC SHALL BE RESPONSIBLE FOR PROTECTION OF EXISTING MATERIAL AND EQUIPMENT TO REMAIN.
 - 6. ALL EXISTING PIPING AND EQUIPMENT SHOWN MUST BE VERIFIED IN THE FIELD. ANY PLUMBING EQUIPMENT NOT SHOWN SHALL BE BROUGHT TO THE ENGINEERS ATTENTION PRIOR TO REMOVAL.



WATERLINE PROFILE (AT LATERAL)
SCALE: 1" = 50'-0" (H), 1" = 5' (V)

CONSOLIDATED
ENGINEERS
1022 James Drive
Leesport, PA 17033
Tel: 610-916-1600 Fax: 610-916-1610
Internet: www.consolidatedengineers.com



AEM ARCHITECTS INC.
3700 PERKINSMEN AVENUE, READING, PA 19606-2795
Phone: 610-779-3620 Fax: 610-779-3622
www.aem-reading.com

SITE PLAN - PLUMBING
RENOVATIONS TO THE
REAMSTOWN ELEMENTARY SCHOOL
COCALICO SCHOOL DISTRICT
SOUTH REAMSTOWN ROAD, REAMSTOWN, PENNSYLVANIA, LANCASTER COUNTY, PA

ALL DIMENSIONS AND EXISTING CONDITIONS
SHALL BE CHECKED AND VERIFIED
BY THE CONTRACTOR AT THE SITE.
JOB NO.: 22011.00
DRAWN BY: SA
DATE: 04.14.23