




1 IT ROOM 012
3/4" = 1'-0"



3 IT ROOM ELEVATION 012
1/2" = 1'-0"



4 IT ROOM ELEVATION 012
1/2" = 1'-0"



5 RACK ELEVATION DETAIL
N.T.S.

KEY NOTE LEGEND

1	PROVIDE 2-POST RACK, WITH 6" VERTICAL CABLE MANAGEMENT AT THE ENDS OF EACH RACK ROW AND 8" VERTICAL CABLE MANAGEMENT IN BETWEEN RACKS. EACH RACK SHALL BE FASTENED TO THE FLOOR AND GROUNDED TO TMGB OR TGB.
2	PROVIDE 3/4" AC GRADE PLYWOOD, VOID-FREE WITH THE A-SIDE OUT. PAINT WITH OFF-WHITE FIRE-RETARDANT PAINT ON FACE AND EDGES. DO NOT PAINT OVER FIRE-RATED STAMP. MOUNT AT 6" AFF TO 8'-6" AFF.
3	PROVIDE 9" WIDE CABLE RUNWAY. SECURE TO WALLS AND RACKS. GROUND TO TGB.
4	CABLE RUNWAY RADIUS DROP, MOUNTS TO RUNWAY CROSS MEMBER
5	CABLE RUNWAY ELEVATION BRACKET WITH X" STAND-OFF FROM TOP OF THE EQUIPMENT RACK
6	2 RU FIBER OPTIC SPLICE ENCLOSURE
7	2 RU HIGH-DENSITY HORIZONTAL CABLE MANAGER
8	48-PORT 2 RU MODULAR CATEGORY CABLE PATCH PANEL
9	ACCESS CONTROL DOOR CONTROLLER PANEL LOCATION. SEE TY-SERIES.
10	PROVIDE TELECOMMUNICATIONS GROUNDINGS BUSBAR, MOUNT AT 24" AFF.



BrightTree
STUDIOS
301 BRUSH CREEK RD
WARRENDALE, PA 15086
412-212-7515

VERIFY SCALE

BAR IS ONE (1) INCH LONG
ON ORIGINAL DRAWING:

0 1

IF BAR IS NOT ONE (1) INCH LONG,
ADJUST SCALE ACCORDINGLY

CONTRACTOR SHALL FIELD VERIFY
ALL DIMENSIONS.
VARIANCE FROM CONTRACT
DOCUMENTS NOT PERMITTED
WITHOUT PROFESSIONAL & BUREAU
OF CONSTRUCTION APPROVAL.

DRAWN BY
CF

CHECKED BY
DV

DATE
27 JUNE 2023

SCALE
NTS

SHEET No.

TT-301

RECORD REVISIONS



PROFESSIONAL'S SIGNATURE DATE

UpStreet ARCHITECTS, INC.
541 PHILADELPHIA ST. 911 MENOHER BLVD.
INDIANA, PA 15701 JOHNSTOWN, PA 15905

COMMONWEALTH OF PENNSYLVANIA
DEPARTMENT OF GENERAL SERVICES
HARRISBURG, PENNSYLVANIA

D.G.S. PROJECT No.
C-0588-0015 PHASE 1

**LOYSVILLE YOUTH DEVELOPMENT CENTER-
RENOVATIONS TO ZIMMERMAN-
BINGAMAN (ZB) COTTAGE**
DEPARTMENT of HUMAN SERVICES
LOYSVILLE, TYRONE TOWNSHIP, PERRY COUNTY, PA

TELECOM ENLARGED PLANS