

PROJECT: HARRISBURG AREA COMMUNITY COLLEGE
J. Evans Physical Education Building - Pool Decommissioning

DATE: January 5, 2024

SUBJECT: ADDENDUM NO. 2

This Addendum will amend, modify, or clarify the Construction Documents and Project Manual. Receipt of this Addendum must be acknowledged on the Bid Form. All bidders are responsible to determine if Addendum items affect their scope of work.

GENERAL:

1. Bid Date:
 - a. The bid date has not changed and remains **January 09, 2024, 10 am via Penn Bid.**
2. Electronic Bids:
 - a. **Bids shall be submitted electronically:**
<https://pennbid.bonfirehub.com/portal/?tab=login>
3. Bidder questions from preconstruction meeting of December 19, 2023, and update to Addendum, No. 1 dated January 2, 2024.
 - a. **Have any tests for ACM's been completed? Yes, the results have been received by the College and no ACMs have been detected in the work area.**
4. Pool Scope Clarifications:
 - a. **What constitutes the need for tile removal?** Any loose tile that is physically detached from the existing setting bed shall be removed and discarded. Any depressions left in the floor shall be flash-patched with an acrylic modified cementitious material such as Acryl 60 or BaseCrete to provide a uniform surface to accept the required vapor barrier and subsequent placement of the new concrete structural floor slab. **Addition: The contractor shall sound all areas of existing ceramic tile flooring, and if tile is found to be loose, it shall be removed to the base level of the existing concrete slab and flash-patched as noted above.**

CLARIFICATIONS TO SPECIFICATIONS AND DRAWINGS:

SPECIFICATIONS:

No modifications to the Architectural and MEP Specifications have been issued.

DRAWINGS:

No modifications to the Architectural and MEP drawings have been issued.

CLARIFICATIONS TO THE SCOPE OF WORK

None.

END ADDENDUM NO. 2

Attachments: None