


KEYED DEMOLITION NOTES

- 1 REMOVE TRAILER MOUNTED BOILER. BOILER TO BE REMOVED FROM SHELL OF TRAILER. SEA CAN CONTAINER TO BE REMOVED AND DISPOSED OF BY CONTRACTOR. TRAILER CHASSIS IS TO REMAIN ON SITE AS THE CHASSIS IS TITLED TO THE COMMONWEALTH OF PENNSYLVANIA. SEE SEQ. 2 NEW WORK PLAN FOR ADDITIONAL INFORMATION ON RELOCATION OF BOILER. ALL ASSOCIATED BOILER FEED, CONDENSATE, GAS, FUEL OIL, ETC. CONNECTIONS SHALL BE REMOVED BACK TO EACH RESPECTIVE MAIN. COORDINATE EXACT PIPING REMOVALS WITH TEMPORARY 300 BHP BOILER PIPING NETWORKS.
- 2 REMOVE BOILER FEEDWATER PUMP IN ENTIRETY AND ASSOCIATED PIPING AS SHOWN. HOUSEKEEPING PAD SHALL BE REMOVED BY .1 CONTRACTOR.
- 3 REMOVE CHEMICAL TREATMENT SYSTEM AND ASSOCIATED APPURTENANCES IN ENTIRETY.
- 4 REMOVE CONDENSATE PUMP IN ENTIRETY AND ASSOCIATED PIPING AS SHOWN.
- 5 REMOVE 3\"/>

1 OPERATING FLOOR LEVEL PLAN - SEQUENCE 2 MECHANICAL DEMOLITION
H-8 SCALE: 1/4\"/>



REBID SUBMISSION
FEBRUARY 26, 2024

| | |
|--|--|
| RECORD REVISIONS | |
| | |
| SIGNATURE DATE | |
| ARRIS ENGINEERING GROUP, LTD. 667 SOUTH RIVER STREET PLAINS, PENNSYLVANIA | |
| COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF GENERAL SERVICES HARRISBURG, PENNSYLVANIA | |
| D.G.S. PROJECT No. C-0304-0015 PHASE 2 | |
| ELIZABETHTOWN TRAINING ACADEMY - RENOVATE BOILER PLANT AND DOMESTIC / FIRE PROTECTION PIPING | |
| DEPARTMENT OF CORRECTIONS ELIZABETHTOWN, LANCASTER COUNTY, PA | |
| OPERATING FLOOR LEVEL PLAN - SEQUENCE 2 MECHANICAL DEMOLITION | |
| DRAWN BY DATE DRAWING No. MTD FEB 2023 H-8 | |
| CHECKED BY SCALE RS AS NOTED | |

VERIFY SCALE
BAR IS ONE (1) INCH LONG
ON ORIGINAL DRAWING:
0 1
IF BAR IS NOT ONE (1) INCH LONG,
ADJUST SCALE ACCORDINGLY
CONTRACTOR SHALL FIELD VERIFY
ALL DIMENSIONS.
VARIANCE FROM CONTRACT
DOCUMENTS NOT PERMITTED
WITHOUT PROFESSIONAL & BUREAU
OF CONSTRUCTION APPROVAL.