



1. .4 CONTRACTOR SHALL COORDINATE ALL REMOVALS WITH OTHER TRADES.
2. .4 CONTRACTOR SHALL REMOVE ALL ELECTRICAL EQUIPMENT INCLUDING ALL EXPOSED CONDUIT AND WIRING FROM SOURCE PANELS AND TO EQUIPMENT LOADS.
3. ALL PATCHING OF FLOORS AND WALLS (TO MATCH EXISTING) BY .1 CONTRACTOR UNLESS NOTED OTHERWISE.
4. VERIFY ALL CONDUIT ROUTING IN FIELD.



- 1 REMOVE EMERGENCY GENERATOR, WIRING, AND CONDUIT TO ATS IN ITS ENTIRETY. CUT GENSET FRAME AS NEAR TO PANEL MDP AS REQUIRED TO ALLOW ADEQUATE SPACE FOR NEW EQUIPMENT TO BE INSTALLED UNDER SEQUENCE 1 NEW WORK. PROVIDE TEMPORARY SUPPORT OF REMAINING FRAME AS REQUIRED.
- 2 REMOVE ATS IN ITS ENTIRETY.
- 3 BOILER REMOVAL (INCLUDING BOILER CONTROL PANEL) IN ITS ENTIRETY BY .2 CONTRACTOR. REMOVE BOILER STOKER FEEDS/ALL ELECTRICAL APPURTENANCES, WIRING & EXPOSED CONDUIT BACK TO SOURCE PANEL(S) IN THEIR ENTIRETY. COORDINATE ALL WORK WITH .2 CONTRACTOR.
- 4 BOILER FEED WATER PUMP REMOVAL BY .2 CONTRACTOR. REMOVE PUMP DISCONNECT/STARTER INCLUDING WIRING BACK TO SOURCE.
- 5 REMOVE ABANDONED EQUIPMENT INDICATED BY THIS NOTE INCLUDING OVERHEAD FEEDERS BACK TO PUMP HOUSE SOURCE ENTIRELY. TURN OVER ALL EQUIPMENT/CABLING TO CLIENT AGENCY.
- 6 ABOVE MEZZANINE TO BE REMOVED BY .1 CONTRACTOR. REMOVE ALL MEZZANINE MTD. LIGHTING FIXTURES, WIRING AND CONDUIT. PROVIDE TEMPORARY LIGHTING AS REQUIRED THROUGHOUT SPACE UNTIL INSTALLATION OF NEW LIGHTING FIXTURES IS COMPLETE. RE: SEQUENCE 1 NEW WORK PLAN.
- 7 ABOVE MEZZANINE REMOVAL/RECONFIGURATION BY .1 CONTRACTOR. COORDINATE ALL TEMPORARY AND PERMANENT REMOVALS/MODIFICATIONS TO .1 LOW VOLTAGE SYSTEMS (I/T, FIRE ALARM, SECURITY) WITH RESPECTIVE VENDORS (CLIENT AGENCY I.T. DEPARTMENT, VECTOR FIRE & SECURITY [CONTACT: JIM LORAH jlarah@vectorsecurity.com] & CLIENT AGENCY SECURITY DEPARTMENT) FOR DEVICES AND CONDUIT SUPPORTED BY/MOUNTED TO/RENDERED USELESS BY MEZZANINE ALTERATIONS.
- 8 REMOVE FUSES AND ALL WIRING ASSOCIATED WITH 4 CIRCUIT POWER PANEL "PP. PROVIDE FLUSH PLATE COVER OVER PANEL AFTER TRANSFER OF LOADS TO NEW PANEL "PP1. RE: SEQUENCE 1 NEW WORK PLAN.
- 9 REMOVE LIGHTING FIXTURES INCLUDING WIRING AND CONDUIT BACK TO SOURCE. PROVIDE TEMPORARY LIGHTING AS REQUIRED THROUGHOUT SPACE UNTIL INSTALLATION OF NEW LIGHTING FIXTURES IS COMPLETE. RE: SEQUENCE 1 NEW WORK PLAN.
- 10 REMOVE BUILDING MTD. EXTERIOR LIGHTING FIXTURE, WIRING AND CONDUIT BACK TO SOURCE AFTER INSTALLATION OF NEW EXTERIOR LIGHTING FIXTURES IS COMPLETE. RE: SEQUENCE 1 NEW WORK PLAN.
- 11 REMOVE ALL RECEPTACLES AND LIGHT SWITCHES WITHIN BUILDING INTERIOR AND PROVIDE BLANK COVER PLATE OVER RECESSED BACK BOXES. SURFACE MOUNTED BACK BOXES TO BE REMOVED ENTIRELY. ABANDON ALL CONCEALED WIRING WITHIN WALLS AND FLOOR. REMOVE ALL EXPOSED CONDUIT AND WIRING ASSOCIATED WITH RECEPTACLES. NOT ALL DEVICES SHOWN ON PLAN.
- 12 .4 CONTRACTOR TO RE-ROUTE EXISTING FIRE ALARM CONDUIT DOWN TO BASEMENT LEVEL FOR INSTALLATION OF NEW DOOR BY .1 CONTRACTOR. MODIFY EXISTING CONDUIT/PROVIDE NEW CONDUIT AS REQUIRED AND COORDINATE ALL WORK WITH FIRE ALARM VENDOR. REFER TO SEQUENCE 1 NEW WORK PLAN FOR PROPOSED LOCATION OF CONDUIT DROP.
- 13 COAL SILO REMOVED IN ITS ENTIRETY BY .1 CONTRACTOR. REMOVE ALL ELECTRICAL APPURTENANCES, LIGHTING FIXTURES, CONDUIT AND WIRING ASSOCIATED WITH COAL SILO.

REBID SUBMISSION
FEBRUARY 26, 2024

RECORD REVISIONS



02-26-2024

SIGNATURE DATE

ARRIS ENGINEERING GROUP, LTD.
667 SOUTH RIVER STREET
PLAINS, PENNSYLVANIA

COMMONWEALTH OF PENNSYLVANIA
DEPARTMENT OF GENERAL SERVICES
HARRISBURG, PENNSYLVANIA

D.G.S. PROJECT No. C-0304-0015 PHASE 2

ELIZABETHTOWN TRAINING ACADEMY – RENOVATE
BOILER PLANT AND DOMESTIC / FIRE PROTECTION
PIPING

DEPARTMENT of CORRECTIONS
ELIZABETHTOWN, LANCASTER COUNTY, PA

OPERATING FLOOR LEVEL -

SEQUENCE 1
ELECTRICAL DEMOLITION PLAN

BY	DRAWN BY	DATE	DRAWING No.
----	----------	------	-------------

S LOVE	FEB 2023	E-3
CHECKED BY	SCALE	

AU	R SZATKOWSKI	AS NOTED
----	--------------	----------

VERIFY SCALE

BAR IS ONE (1) INCH LONG
ON ORIGINAL DRAWING:

0 1

IF BAR IS NOT ONE (1) INCH LONG
ADJUST SCALE ACCORDINGLY

CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.
VARIANCE FROM CONTRACT

VARIANCE FROM CONTRACT
DOCUMENTS NOT PERMITTED
WITHOUT PROFESSIONAL & BUREAU
OF CONSTRUCTION APPROVAL

DATE	11/11/2011
BY	11/11/2011
DRAWN BY	S LOVE

	CHECKED BY
AU	R SZATKOW

--	--

DATE	FEB 2
------	-------

WSKI	SCALE AS NO
------	----------------

DRAWING No.	
-------------	--

1

E-3

FILE PATH: F:\400.01 0304-2015 P2 Elizabethtown Boiler\Drawings\No Base Bld Drawings\4-Electrical (C)\E-3_Seq.1 Operating Floor Level Electrical Demolition Plan.dwg