


KEYED CONSTRUCTION NOTES

- RELOCATE AND INSTALL EXISTING 350 BHP TRAILER MOUNTED BOILER.
- CONNECT ALL PIPING FROM EXISTING AND NEW SYSTEMS INCLUDED BUT NOT LIMITED TO EXISTING STEAM PIPING, NATURAL GAS, FEEDWATER, BLOWDOWN PIPING, ETC. TO FORM A FULLY OPERATIONAL SYSTEM.
- CONNECT 24" BOILER FLUE TO CAPPED BREECHING CONNECTION INSTALLED WITHIN SEQ. 1.
- 4" VENT UP THROUGH ROOF. UTILIZE EXISTING ROOF PENETRATION. ROOF PENETRATION SHALL BE SEALED BY OTHERS IN COORDINATION WITH THE OWNERS ROOFING CONTRACTOR.
- CONNECT EXISTING 4" STEAM PIPING TO NEW STEAM HEADER ON OPERATING FLOOR.

1 MEZZANINE LEVEL PLAN - SEQUENCE 2 MECHANICAL NEW WORK
H-11 SCALE: 1/4" = 1'-0"



REBID SUBMISSION
FEBRUARY 26, 2024

RECORD REVISIONS	
SIGNATURE DATE	
ARRIS ENGINEERING GROUP, LTD. 667 SOUTH RIVER STREET PLAINS, PENNSYLVANIA	
COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF GENERAL SERVICES HARRISBURG, PENNSYLVANIA	
D.G.S. PROJECT No. C-0304-0015 PHASE 2	
ELIZABETHTOWN TRAINING ACADEMY - RENOVATE BOILER PLANT AND DOMESTIC / FIRE PROTECTION PIPING	
DEPARTMENT OF CORRECTIONS ELIZABETHTOWN, LANCASTER COUNTY, PA	
MEZZANINE LEVEL PLAN - SEQUENCE 2 MECHANICAL NEW WORK	
VERIFY SCALE	
BAR IS ONE (1) INCH LONG ON ORIGINAL DRAWING: 0 1 IF BAR IS NOT ONE (1) INCH LONG, ADJUST SCALE ACCORDINGLY	
CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS. VARIANCE FROM CONTRACT DOCUMENTS NOT PERMITTED WITHOUT PROFESSIONAL & BUREAU OF CONSTRUCTION APPROVAL.	
DRAWN BY MTD	DATE FEB 2023
CHECKED BY RS	SCALE AS NOTED
DRAWING No. H-11	

FILE PATH: F:\V400.01 0304-0015 P2 Elizabethtown Boiler Drawings\3 Mechanical CDV-11 Mezz Floor Plan - Phase 2 New Work.dwg
LAST SAVED: 2024.02.23 12:21 PM