



- GENERAL CONSTRUCTION NOTES
- COORDINATE SEQUENCE OF WORK WITH ALL TRADES PRIOR TO START OF CONSTRUCTION WORK
 - ALL ROOF PATCHING FROM REMOVALS TO BE DONE BY CLIENT AGENCY CONTRACTOR
 - IF PIPING OR CONDUIT IS REMOVED BY OTHERS .1 CONTRACTORS IS TO SEAL OPENINGS
 - FOR PATCHING OF OPENINGS GREATER THAN ONE INCH SEE DETAIL 2/A-10 AND SECTION 040322 BRICK MASONRY REPAIR. KEY NEW BRICK INTO EXISTING BRICK.
 - FOR PATCHING OF OPENINGS LESS THAN ONE (1") INCH, SEE SECTION 040322 BRICK MASONRY REPAIR, PARAGRAPH: BRICK MASONRY PATCHING.

KEYED CONSTRUCTION NOTES

- PROVIDE INSULATED EXTERIOR DOOR AND FRAME, SEE DOOR SCHEDULE A-10
- PROVIDE MASONRY INFILL, SEE DETAIL 2/A-10
- PROVIDE 4" CMU WALLS
- PROVIDE BAR GRATING AND FRAMES, SEE STRUCTURAL DRAWINGS
- PROVIDE RAINWATER LEADERS TO DAYLIGHT, DIRECT WATER AWAY FROM BUILDING
- PROVIDE PIPE AND TUBE RAILING, SEE DETAIL 10/A-10
- PROVIDE HOUSEKEEPING PAD FOR NEW EQUIPMENT FURNISHED AND INSTALLED BY .2 CONTRACTOR. REFER TO STRUCTURAL DRAWINGS.
- PROVIDE CONCRETE INFILL. REFER TO STRUCTURAL DRAWINGS

REBID SUBMISSION
FEBRUARY 26, 2024

RECORD REVISIONS



ARRIS ENGINEERING GROUP, LTD.
667 SOUTH RIVER STREET
PLAINS, PENNSYLVANIA

COMMONWEALTH OF PENNSYLVANIA
DEPARTMENT OF GENERAL SERVICES
HARRISBURG, PENNSYLVANIA

D.G.S. PROJECT No.
C-0304-0015 PHASE 2
ELIZABETHTOWN TRAINING ACADEMY - RENOVATE
BOILER PLANT AND DOMESTIC / FIRE PROTECTION
PIPING
DEPARTMENT of GENERAL SERVICES
ELIZABETHTOWN, LANCASTER COUNTY, PA

OPERATING FLOOR LEVEL NEW
WORK PLAN

VERIFY SCALE

BAR IS ONE (1) INCH LONG
ON ORIGINAL DRAWING.

0 1
IF BAR IS NOT ONE (1) INCH LONG,
ADJUST SCALE ACCORDINGLY

CONTRACTOR SHALL FIELD VERIFY
ALL DIMENSIONS.
VARIANCE FROM CONTRACT
DOCUMENTS NOT PERMITTED
WITHOUT PROFESSIONAL & BUREAU
OF CONSTRUCTION APPROVAL.

DRAWN BY
VS

DATE
FEB 2024

DRAWING No.
A-6

CHECKED BY
MB

SCALE
AS NOTED

1 OPERATING FLOOR LEVEL NEW WORK PLAN
A-6 SCALE: 1/4" = 1'-0"

