



NOTES : 1. SEE PLANS FOR STRUCTURAL LINTEL LENGTHS AND LOCATIONS.



WOOD JAMB SCHEDULE				
R.O.	WALL STUDS	QTY. JACK STUDS	QTY. KING STUDS	COMMENTS
3'-4"	2x8	(1)	(1)	
3'-4"	2x8	(1)	(1)	
1 2'-10 1/2"	2x8	(1)	(2)	

WALL SHEATHING SCHEDULE					
EDGE FASTENING	SPACING	PANEL FASTENING	SPACING	SHEATHING	REMARKS
8d NAILS	6"o.c.	8d NAILS	12"o.c.	1/2" STRUCTURAL RATED	

ROOF SHEATHING SCHEDULE					
EDGE FASTENING	SPACING	PANEL FASTENING	SPACING	SHEATHING	REMARKS
8d NAILS	6' o.c.	8d NAILS	12' o.c.	3/4" PLYWOOD	

426 SOUTH THIRD STREET  
SUITE 101  
LEMOYNE, PA  
(717) 920-2282  
(717) 920-2284 FAX



STORAGE/MAINTENANCE BUILDING  
SHIREMANSTOWN BOROUGH  
201 RR E MAIN STREET  
SHIREMANSTOWN BOROUGH PA

## STRUCTURAL SCHEDULES & DETAILS

Reproduction of the material herein for substantial use without written permission of KD3 Design Studio, Inc., violates the Copyright Laws of the United States and will be subject to legal prosecution. Copyright: 2024	
DATE :	01/08/24
SCALE :	AS NOTED
JOB NO. :	544-23 KBRACE23056

S401