

1

SECOND FLOOR PLAN - PLUMBING


SCALE: 1/4" = 1'-0"

0

1/2'

1'

1 1/2'



- GENERAL SHEET NOTES
- A. MAINTAIN SPACE FOR SERVICE AND MAINTENANCE OF EQUIPMENT.
 - B. PROTECT DRAINS DURING REMAINDER OF CONSTRUCTION PERIOD TO AVOID CLOGGING WITH DIRT AND DEBRIS AND TO PREVENT DAMAGE FROM TRAFFIC AND CONSTRUCTION WORK.
 - C. PLACE PLUGS IN ENDS OF UNCOMPLETED PIPING AT END OF DAY AND WHEN WORK STOPS.
 - D. INSTALL ISOLATION VALVES ON EACH BRANCH CONNECTION.
 - E. INSTALL SANITARY SLOPED AT MAXIMUM SLOPE TO THE SITE INVERT CONNECTION FROM STARTING CONNECTION. MAINTAIN A MINIMUM OF 1/4" FALL PER FOOT.
 - F. USE A MINIMUM OF 2" OR GREATER PIPING BELOW GRADE FOR SANITARY.
 - G. ROUGH-IN PIPING SERVICES FOR FIXTURES. MOUNT FIXTURES ACCORDING TO CONTRACT DOCUMENTS, LOCAL CODES AND ADA REQUIREMENTS.
 - H. FURNISH AND INSTALL CLEANOUTS AT THE BASE OF EACH STACK.
 - I. REFER TO STRUCTURAL DRAWINGS FOR SEISMIC CLASSIFICATION FOR BUILDING. FURNISH AND INSTALL SEISMIC HANGERS AND SUPPORTS AS REQUIRED.

**GREEN BUILDING ENGINEERS**

2548 Brandywine Lane, York, PA 17404
412-841-4901 717-554-0153



426 S THIRD STREET
SUITE 101
LEMOYNE, PA 17043
717-920-2282
KDBDESIGNSTUDIO.COM

KDB
DESIGN STUDIO

STORAGE/MAINTENANCE BUILDING
SHIREMANSTOWN BOROUGH
201 RR E MAIN STREET
SHIREMANSTOWN BOROUGH, PA

SECOND FLOOR PLAN - PLUMBING

Reproduction of the material herein or substantial use without written permission of KDB Design Studio, Inc., violates the Copyright Laws of the United States and will be subject to legal prosecution. Copyright, 2024

DATE : 01/08/2024

SCALE : AS NOTED

JOB NO: 544-23

SHEET

P-102