


GENERAL SHEET NOTES

- A. SEE ARCHITECTURAL PLANS FOR REFLECTED CEILING PLAN, AND DIMENSIONED LOCATIONS OF LIGHTING FIXTURES.
- B. LIGHTING CONTROLS TO MEET REQUIREMENTS OF IECG STANDARDS.
- C. LIGHTING SWITCHES 40" ABOVE FINISHED FLOOR UNLESS NOTED OTHERWISE.
- D. OCCUPANCY SENSOR CONTROLS TO BE SET TO TURN LIGHTING OFF AFTER 30 MINUTES.
- E. PROVIDE 0-10V DIMMING SIGNAL DEVICE AND WIRING TO CONNECTED FIXTURES FOR DIMMER SWITCHES UNLESS NOTED OTHERWISE.
- F. REMOTE OCCUPANCY SENSORS SHALL BE LOCATED TO PROVIDE FULL ROOM COVERAGE OF OCCUPANT SENSING. PROVIDE COMPONENTS, WIRING AND CONNECTIONS FOR A FUNCTIONAL ROOM LIGHTING CONTROL SYSTEM WITH SWITCHES AND DIMMERS AS SHOWN.
- G. CONNECT EXIT SIGNS AND EMERGENCY LIGHTING TO LOCAL LIGHTING CIRCUIT.
- H. EXIT SIGNS SHALL BE ALWAYS ON.
- I. PROVIDE UNSWITCHED LINE VOLTAGE WIRING TO EMERGENCY BACKUP FIXTURES DESIGNATED "EM".
- J. PROVIDE PHOTOCELL CONTROL FOR EXTERIOR FIXTURES.
- K. PROVIDE ELECTRONIC TIMER WITH PROGRAMMABLE ON/OFF TIMES, AND LIGHTING POWER REDUCTION IN ACCORDANCE WITH IECG REQUIREMENTS FOR EXTERIOR DECORATIVE, LANDSCAPING AND FEATURE HIGHLIGHTING FIXTURES.




1 SECOND FLOOR PLAN - LIGHTING

SCALE: 1/4" = 1'-0"

0 2' 4' 8'

**GREEN BUILDING ENGINEERS**

2548 Brandywine Lane, York, PA 17404
412-841-4901 717-554-0153



426 S THIRD STREET
SUITE 101
LEMOYNE, PA 17043
717-920-2282
KDBDESIGNSTUDIO.COM

**DESIGN STUDIO**

STORAGE/MAINTENANCE BUILDING
SHIREMANSTOWN BOROUGH
201 RR E MAIN STREET
SHIREMANSTOWN BOROUGH, PA

SECOND FLOOR - LIGHTING

Reproduction of the material herein or substantial use without written permission of KDB Design Studio, Inc., violates the Copyright Laws of the United States and will be subject to legal prosecution. Copyright, 2024

DATE :	01/08/2024
SCALE :	AS NOTED
JOB NO:	544-23

SHEET

E-102