

FIRST FLOOR PLAN - UNIT B - PLUMBING
SCALE: 1/8" = 1'-0"


THE PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL ELECTRICAL PANEL LOCATIONS (INSIDE ELECTRICAL AND OUTSIDE ELECTRICAL ROOMS) WITH PIPING LAYOUTS PRIOR TO PIPING INSTALLATION. THE PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING ALL N.E.C. (NATIONAL ELECTRIC CODE) CLEARANCES BEFORE INSTALLING ANY PIPING. THE PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ANY AND ALL COSTS RESULTING TO REWORKING (REMOVING AND REINSTALLING) PIPING INSTALLED IN CONFLICT WITH ELECTRICAL PANELS/EQUIPMENT CLEARANCES.

DRAWING NOTES:

1. PROVIDE THE MINIMUM REQUIRED SERVICE CLEARANCES FOR ALL EQUIPMENT AS RECOMMENDED BY THE EQUIPMENT MANUFACTURER.
2. ALL OVERHEAD DOMESTIC WATER, SANITARY AND VENT PIPING MUST BE ROUTED EITHER UP IN BETWEEN BAR JOIST OR THROUGH BAR JOIST WEBBING UNLESS OTHERWISE NOTED.

KEYED DRAWING NOTES:

1. REMOVE EXISTING BALANCING VALVE AND PROVIDE NEW CALIBRATED BALANCING VALVE, SHUT-OFF AND CHECK VALVES. ADJUST FLOW FOR 1.0 GPM.
2. PROVIDE CALIBRATED BALANCING VALVE, SHUT-OFF AND CHECK VALVES. ADJUST FLOW FOR 0.5 GPM.
3. PROVIDE CALIBRATED BALANCING VALVE, SHUT-OFF AND CHECK VALVES. ADJUST FLOW FOR 1.0 GPM.
4. PROVIDE CALIBRATED BALANCING VALVE, SHUT-OFF AND CHECK VALVES. ADJUST FLOW FOR 1.5 GPM.
5. PROVIDE CALIBRATED BALANCING VALVE, SHUT-OFF AND CHECK VALVES. ADJUST FLOW FOR 2.0 GPM.



FIRST FLOOR PLAN - UNIT B - PLUMBING
RENOVATIONS TO THE COCALICO MIDDLE SCHOOL
COCALICO SCHOOL DISTRICT
SOUTH 4TH STREET, DENVER BOROUGH, LANCASTER COUNTY, PA

ALL DIMENSIONS AND EXISTING CONDITIONS
SHALL BE CHECKED AND VERIFIED
BY THE CONTRACTOR AT THE SITE.

JOB NO.: 23001.00
DRAWN BY: SA
DATE: 04.12.24

P-B1

CONSOLIDATED
ENGINEERS
1022 James Drive
Leesport, PA 19533
Tel: 610/941-6100 Fax: 610/941-6101
Internet: www.consolidatedengineers.com

CIE

COMMONWEALTH OF
PENNSYLVANIA
REGISTERED PROFESSIONAL
ENGINEER
ADAM NICHOLAS MOSER
No. 0074840
Exp. 12/31/2025

AEM ARCHITECTS, INC.
3700 PERKINS AVENUE, READING, PA 19606-2785
Phone: 610/79-3220 Fax: 610/79-3822
www.aem-arch.com