


1
P-3
SITE PLAN - PLUMBING
SCALE: 1" = 40'-0"

NUMBERED NOTES: ④ (THIS SHEET ONLY)

- 1 EXTEND & CONNECT 6" PVC SANITARY TO EXISTING 8" PVC SANITARY. CAMERA THE EXISTING LINE TO VERIFY LOCATION AND DEPTH PRIOR TO EXCAVATION.
- 2 EXTEND & CONNECT 8" PVC STORM DRAIN TO EXISTING INLET MIN 36" BFG. CAMERA THE EXISTING DRAIN TO VERIFY LOCATION AND DEPTH PRIOR TO EXCAVATION.
- 3 EXTEND & CONNECT 4" DUCTILE IRON WATER LINE TO EXISTING 4" LINE MIN. 42"BFG. VERIFY LOCATION AND DEPTH PRIOR TO EXCAVATION.
- 4 EXTEND 1" HDPE WATER LINE FROM FIELDHOUSE TO TICKET BOOTH MIN.42" BFG IN CONTINUOUS PIPE WITHOUT FITTINGS.



VENT THRU ROOF DETAIL - TYPICAL
NO SCALE

